

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dicks of Skelly has this

date requested permission to plug the following described well:

Mr. Dicks guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company

Complete Address: 1860 lincoln St., Denver, Colo.

Lease Name: Raymond Vail Well No. 1

Location: C SE SE Sec. 29 Twp. 32 Rge. 30 XX (E) (W)

County: Meade Total Depth 5700' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Dicks. was instructed to plug the well as follows:

9 5/8" to 1570' circulated w/ cement. 5 1/2" to 5699' cemented.

Top perforations 5559' Plug bottom w/ 35 sacks cement.

Top of cement 4703' Mud 4703' to 1000'

Spot 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent