

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 22 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Texas Energies has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Texas Energies Inc.

Complete Address: 306 Bank of SW., Amarillo, Texas

Lease Name: Williamson Well No. 1

Location: C SE SE Sec. 12 Twp. 32 Rge. 31 (E) (W)

County: Seward Total Depth 5673' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1600' circuted w/ cement. 5 1/2" casing to 5673' cemented.

Top perforations 5502' Plug bottom w/ 20 sacks cement.

Top of cement 5400' Mud 5400' to 900'

Spotted 35 Cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent