



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent) STATE CORPORATION COMMISSION

RECEIVED  
JAN 6 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of William Gruenerwald has this date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: William Gruenerwald & Assoc.

Complete Address: Box 909, Colorado, Springs, Colorado 80901

Lease Name: Woodworth Well No. 1

Location: SW NE Sec. 6 Twp. 32 Rge. 31 (E) (W)

County: Seward Total Depth 5975' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1638' circulated w/ cement. 2 7/8" to 5974' cemented.


Top perforations 4971' Plug bottom w/ 8 sacks cement

Top of cement 4000' Mud 4000' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent