

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
AUG 18 1969
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Armstrong of Yucca Petroleum has this
date requested permission to plug the following described well:

Mr. Armstrong guarantees payment of the plugging fee.

Operator's full Name: Yucca Petroleum Co.

Complete Address: Box 2585, Amarillo, Texas

Lease Name: Tendick Well No. 1

Location: C SW NW Sec. 27 Twp. 32 Rge. 31 (E) (W)

County Seward Total Depth 5986' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Armstrong was instructed to plug the well as follows:

- 8 5/8" to 1616' circulated w/cement, Mud 5986' to 5973'
- Spot 50 sacks cement 5973' to 5781' Mud 5781' to 1636'
- Spot 50 sacks cement 1636' to 1455' Mud 1455' to 30'
- Plug, Hulls & 15 sacks cement 30' to 0'.

INVOICED

DATE _____
INV. NO. _____

Very truly yours,

Edward E. Evers
Conservation Division Agent