

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

MAY 3 1968

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Hannah of Anadarko Production has this

date requested permission to plug the following described well:

Mr. Hannah guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name: Richardson Well No. 1

Location: SW SE Sec. 26 Twp. 32 Rge. 31 (W)

County Seward Total Depth 5982' Oil Well

Gas Well X Input Well  SWD Well  D & A X Lost Hole

Mr. Hannah was instructed to plug the well as follows:

8 5/8" to 1572' circulated w/ cement. 4 1/2" to 5754' cemented.

Top perforations 5565' Plug bottom w/ 15 sacks cement.

Top of cement 4900' Mud 4900' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 40'

Plug, Halls & 15 sacks cement 40' to 0'

Very truly yours,

Conservation Division Agent