

KANSAS

*P*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 24 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company

Complete Address 915 Union Nat'l Bldg., Wichita, Kansas

Lease Name Krause Well No. 1

Location C SW SW Sec. 36 Twp. 32 Rge. 30 (EX) (W)

County Meade Total Depth 5835'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Sargents Casing Pulling Co.

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 2:30Pm Day 17 Month 2 Year 1971

The above well was plugged as follows:

8 5/8" to 1629' circulated w/ cement. 5 1/2" to 5750' cemented.

Top perforations 5666' Plug bottom w/ 20 sacks cement

Top of cement 5500' Mud 5500' to 1000'

Spotted 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Halls & 15 sacks cement 45' to 0'. Company Pump

Pulled 3107' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edgar J. Cook*  
Well Plugging Supervisor

DATE 2/25/71  
INV. NO. 3373-W