

15-119-10080-0000

Form CP-3  
Rev. 6-26-62

*Y*  
KANSAS  
STATE CORPORATION COMMISSION  
RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

MAY 24 1966

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Graham-Michaelis Drilling Company

Complete Address: 211 N. Broadway, Wichita, Kansas

Lease Name Jones "B" Well No. 1

Location C SE SE Sec. 34 Twp. 32 Rge. 30 (~~EX~~) (W)

County Meade Total Depth 5820'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 7:00PM Day 21 Month 5 Year 1966

The Above well was plugged as follows:

8 5/8" to 1545' circulated w/ cement. 5 1/2" to 5819' cemented.

Top Perf. 5702' Plug bottom w/ 20 sacks cement.

Top of cement 5600' Mud 5600' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 45'

Plug, Hulls & 15 sacks cement 45' to 0' Welded Plate on 8 5/8".

Company Pump. Pulled 3025' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar J. Evers  
Well Plugging Supervisor

DATE 5/24/66

INV. NO. 3268-W