

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Skelly Oil Co.

Complete Address 1860 Lincoln St., Denver, Colo. 80203

Lease Name Raymond Vail Well No. 1

Location 0 SE SE Sec. 29 Twp. 32 Rge. 30 (E) (W)

County Meade Total Depth 5700'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated None

Plugging Contractor Knight Casing Pulling Co.

Address Chase, Kansas License No. 624

Operation Completed: Hour 2:00PM Day 29 Month 9 Year 1971

The above well was plugged as follows:

9 5/8" to 1570' circulated w/ cement. 5 1/2" to 5699' cemented.

Top perforations 5559' Plug bottom w/ 35 sacks cement

Top of cement 4703' Mud 4703' to 1000'

Spot 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Halls & 15 sacks cement 45' to 0'. Halliburton Pump Truck.

Pulled 2704' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edward J. Evers
Well Plugging Supervisor

DATE 10/5/71

INV. NO. 4417-w