



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAY 28 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Trumart Oil Company

Complete Address Box 12, Ellis, Kansas 67637

Lease Name Holmes Estate Well No. 1

Location NE SW SW Sec. 28 Twp. 32 Rge. 30 (E) (W)

County Meade Total Depth 5682'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Saggets Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 4:00PM Day 20 Month 5 Year 1974

The above well was plugged as follows:

13 3/8" to 585' circled w/ cement. 9 5/8" to 2585' cemented.

5 1/2" to 5676' cemented. Top perforations 5540'

Plug bottom w/ 20 sacks cement. Top of cement 5400'

Mud 5400' to 600' Spotted 50 sacks cement 600' to 500'

Mud 500' to 40' Plug, hulls & 20 sacks cement 40' to 0'

Pulled 3008' of 5 1/2" casing & 766' of 9 5/8" casing.

Company Pump _____

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 5/30/74

Signed: Edgar J. Ellis
Well Plugging Supervisor

INV. NO. 9205-W