

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 30 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Colorado Oil & Gas Corp.

Complete Address: Box 158 Liberal, Kansas

Lease Name Collins Well No. # 1

Location SE NE NE Sec. 16 Twp. 32S Rge. 31 (E) (W)

County Seward Total Depth 5749'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Gayle E. Toland

Address: Okla. City, Okla. License No. 539

Operation Completed: Hour 2 PM Day 25 Month 11 Year 64

The Above well was plugged as follows:

8 5/8" - 1400' Circulated w/cement. 5 1/2" - 5749' Cemented. Top perforations - 5600'

Plug bottom w/20 Sax. cement top cement, 5350'. Mud 5350' to 700'

35 Sax. cement: 700' to 600'. Mud 600' to 45'

Plug, 15' Sax. cement 45' to 0 Company Pump. Pulled 2850' 5 1/2" pipe.

Cut surface off 5' below ground level, weld cap on pipe.

I hereby certify that the above well was plugged as herein stated.

DATE 12/1/64  
INV. NO. 234-11

Signed: [Signature]  
Well Plugging Supervisor