

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 22 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Texas Energies Inc.

Complete Address 306 Bank of SW., Amarillo, Texas 79109

Lease Name Williamson Well No. 1

Location C SE SE Sec. 12 Twp. 32 Rge. 31 (E) (W)

County Seward Total Depth 5673'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sargents Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 4:00PM Day 15 Month 1 Year 1974

The above well was plugged as follows:

8 5/8" to 1600' circulated w/ cement. 5 1/2" to 5673' cemented.

Top perforations 5502' Plug bottom w/ 20 sacks cement.

Top of cement 5400' Mud 5400' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2704' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 1/22/74

INV. NO. 8438-W