

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 17 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill,
filed March 27, 1967.

Operator's Full Name Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas

Lease Name Trousdale Well No. # 1

Location C NW SW Sec. 34 Twp. 30 Rge. 5 (E) (W) W

County Kingman Total Depth 4632'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Mack Oil Company

Address: 812 Union Center Bldg., Wichita, Kansas License No.

Operation Completed: Hour 3:00PM Day 13th Month April Year 1967

The Above well was plugged as follows:

236' of 8.5/8" surface pipe, cement circulated with 225 sacks. Hole was
filled with drilling mud to 225', 1st cementing plug, bridged with 1 sack
of Gel-Mud and 1/2 sack of hulls on fluid at 225', and cemented with 30 sacks,
through the drill pipe. Hole was filled with drilling mud to 50', 2nd cem-
enting plug, bridged with 1/2 sack of hulls on fluid at 50', and cemented with
20 sacks to the base of the cellar. Rat and mouse holes bridged and cemented
with 5 sacks.

This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Aurlie Elving
Well Plugging Supervisor

DATE 4/17/67

INV. NO. 5055-W