

15-095-21240-0000

Form CP-3  
Rev. 6-26-62

Y KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

8-21-64  
AUG 21 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name Risley Well No. # 1

Location C NW NW Sec. 3 Twp. 30 Rge. 6 (E) (W) W

County Kingman Total Depth 3060

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A      X     

Other well as hereafter indicated:     

Plugging Contractor: Garvey Drilling Company

Address: Route 2, Great Bend, Kansas License No.     

Operation Completed: Hour 2:45AM Day 20th Month August Year 1964

The Above well was plugged as follows:

256' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole  
was filled with drilling mud to 250', 1st cementing plug, bridged  
with hulls, on fluid at 250', and cemented with 25 sacks. Hole was  
filled with drilling mud to 40', 2nd cementing plug, bridged with  
hulls, on fluid at 40', and cemented with 10 sacks to the base of  
the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 8/21/64  
INV. NO. 9698-W

Signed: Archie Elving  
Well Plugging Supervisor