

M KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 17 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued April 10, 1967.

Operator's Full Name Aladdin Petroleum Corporation

Complete Address: 809 Petroleum Bldg., Wichita, Kansas

Lease Name Dewey Well No. # 1

Location C NE SW Sec. 15 Twp. 30 Rge. 6 (E) (W) W

County Kingman Total Depth 4520'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 5:45PM Day 14th Month April Year 1967

The Above well was plugged as follows:

226' of 8 5/8" surface pipe, cement circulated. 4520' of 4 1/2" long string,
cemented with 75 sacks. Top perferation 4465'. Bottom of the hole was sanded
to 4450', and cemented with 3 sacks, through the dump bailer. 3800' of 4 1/2"
long string was recovered from the hole. Hole had been loaded and was full
of heavy mud. 25 sacks of cement was pumped at 600', through the 4 1/2" long
string. Surface pipe was squeezed. 75 sacks of cement was pumped into the
surface pipe, through an 8 5/8" swage, to a pressure of 50 lbs. Cemant will
be brought to the base of the cellar. This cementing was done by Halliburton
Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Achie Elving
Well Plugging Supervisor

DATE 4/17/67
INV. NO. 5056-W