

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-23-76
JUL 23 1976

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Mack Oil Company

Complete Address PO Box 400, Duncan, Okla. 73533

Lease Name Mies Well No. 1

Location NW SW Sec. 21 Twp. 30 Rge. 3 (W)

County Sumner Total Depth 4316 ^{log shows} 1330

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Chase, Kansas License No. 6803

Operation Completed: Hour 11:30 AM Day 22 Month 7 Year 1976

The above well was plugged as follows: 256' - 8 5/8" - 5 1/2" - 4329' - top perf. 3245'
Pushed plug to 3220', put in 20' sand and
dumped 5 sacks cement in 5 1/2" casing. After
recovering 2130' casing fluid stand at 300' -
Pushed plug to fluid, put in 40' rock and sand
and filled to 30' below ground level with 4 yards
ready mix cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 7-29-76

INV. NO. 236-E