

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
7-20-76  
JUL 20 1976

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Meek Oil Company

Complete Address Box 1500, Duncannon, Okla. 73535

Lease Name Hartman Well No. 1

Location NW 38 Sec. 21 Twp. 30 Rge. 3 (W)

County Sumner Total Depth 4303 acc. to log.

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling

Address Chase, Kansas License No. 683

Operation Completed: Hour 1:45 AM Day 19 Month 7 Year 1976

The above well was plugged as follows: 253' - 8 5/8" - 4 1/2" csg. 4202' top of 4251'

Filled hole with sand to 4225' and dumped 4  
sacks cement with dump bailer. Shot pipe off at  
3700', pulled 6 joints and well blew out. Pumped in  
salt water and circulated oil out hole as well as  
grit. Pulled rest of casing, put in plug at 240  
ft 18" rock bridge. Filled hole with 4 yards  
ready mix to 3' below surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7-29-76

INV. NO. 233-E

Signed: Wayne Graham  
Well Plugging Supervisor