

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-025-00019-0000

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Voth of Frank J. Black has this
date requested permission to plug the following described well:

Mr. Voth guarantees payment of the plugging fee.

Operator's full Name: Frank J. Black

Complete Address: Box 150, McPherson, Kansas

Lease Name: Strodtman Well No. 1

Location: C SE NW Sec. 3 Twp. 31 Rge. 21 (W)

County Clark Total Depth 5218' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Voth was instructed to plug the well as follows:

20" casing to 110' circulated w/ cement. 5 1/2" to 5195' cemented.

No Perforations Plug bottom w/ sand & 5 sacks of cement.

Top of cement 5150' Mud 5150' to 600'

Spot 30 sacks cement 600' to 500' Mud 500' to 130'

Spot 40 sacks cement 130' to 80' Mud 80' to 30'

Plug & 30 sacks cement 30' to 0'

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

Edgar J. Lewis
Conservation Division Agent

JUN - 9 1966

CONSERVATION DIVISION
Wichita, Kansas