

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Crawford of Red Tiger Drlg., Co. has this date requested permission to plug the following described well:

Mr. Crawford guarantees payment of the plugging fee.

Operator's full Name: Gear Pet., Co., Inc.

Complete Address: 300 Sutton Place, Wichita, Ks. 67202

Lease Name: Bailey Well No. 1-A

Location: 50' S/SE SE NE Sec. 18 Twp. 28S Rge. 12 (E)(W)W

County: Pratt Total Depth 4650 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole


Mr. Crawford was instructed to plug the well as follows:

209' 13 3/8" casing W/225 sax cement. 1000' 8 5/8" casing
W/150 sax cement. Pull 435' 8 5/8" casing. Set 50 sax cement
plug at 435'. Set 50 sax cement plug at 190'-Bridge at 40'
& 25 sax cement to 5' below Gl. Cemented by Allied (5 sax
in rat hole.)

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours, **JUL 15 1980**

CONSERVATION DIVISION
Wichita, Kansas


Conservation Division Agent