

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

DEC 14 1966

12-14-66
 CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Frank Pfannenstiel of Leben Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling, Inc.

Complete Address: 815 Wichita Plaza, Wichita, Kansas

Lease Name: Becker Well No. # 1

Location: 150' SW of C SW NE Sec. 8 Twp. 28 Rge. 12 (E)(W) W

County Pratt Total Depth 4595' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pfannenstiel was instructed to plug the well as follows:

360' of 8 5/8" surface pipe, cement circulated with 350 sacks. Fill hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent