



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

15-179-20161-0000

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
9-26-75  
SEP 26 1975

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Jim Reenes of Lillard Casing Pulling has this date requested permission to plug the following described well:

Mr. Reenes guarantees payment of the plugging fee.

Operator's full Name: William J. O'Connor

Complete Address: P.O. Box 16557, Okla. City, Okla

Lease Name: Keeper Well No. 11

Location: C. N. E Sec. 26 Twp. 13 Rge. (E) (W) 13

County: Morton Total Depth 5235 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Reenes was instructed to plug the well as follows:

Surface casing 8 1/8" set to 1528'. Well  
Plugged back to 3258. 4 1/2" casing set to  
3258. Perforations from 2780' to 2784'.  
1st plug 2784' with 70 sacks cement &  
2 sacks cotton seed hulls. 2nd plug at  
1528' with 60 sacks cement.  
3rd plug at 400' with  
15 sacks cement

Very truly yours,

Clarence Thomas