



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-129-00035-0000

RECEIVED
STATE CORPORATION COMMISSION
JUN 15 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Colo Oil has this date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Colorado Oil Company

Complete Address: 915 Union Nat'l Bldg., Wichita, Kansas

Lease Name: Hayward Well No. 1-23

Location: C NE Sec. 23 Twp. 31 Rge. 42 (EX(W))

County: Morton Total Depth 5335' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1509' circulated w/ cement. 5 1/2" to 5318' cemented.


Top perforations 2886' Plug bottom w/ 30 sacks cement.

Top of cement 2619' Mud 2619' to 1000'

Spot 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent