



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-129-10094-0000

RECEIVED  
STATE CORPORATION COMMISSION  
7-5-72  
JUL 5 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Sargent's has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Sargent's Casing Pulling Co.

Complete Address: Box 506, Liberal, Kansas

Lease Name: Baughman Well No. 1

Location: C SW Sec. 28 Twp. 31 Rge. 42 (E)(W)

County: Morton Total Depth 3540' Oil Well

Gas Well X Input Well      SWD Well      D & A      Lost Hole     

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 558' circulated w/ cement. 5 1/2" to 3195' cemented.


Top perforations 2741' Plug bottom w/ 20 sacks cement.

Top of cement 2550' Mud 2550' to 550'

Spot 35 sacks cement 550' to 450'. Mud 450' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent