

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-129-10173-0000

RECEIVED
STATE CORPORATION COMMISSION

JUN 29 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Luck of Thomas & Brewer has this

date requested permission to plug the following described well:

Mr. Luck guarantees payment of the plugging fee.

Operator's full Name: Thomas & Brewer

Complete Address: Box 1177, Liberal, Kansas

Lease Name: Bitner Well No. 1

Location: G NE Sec. 29 Twp. 31 Rge. 42 (E)(W)

County Morton Total Depth 5118' Oil Well X

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Luck was instructed to plug the well as follows:

8 5/8" to 1433' circulated w/ cement. T.D. 5118'

Mud 5118' to 700' Spotted 35 sacks cement 700' to 600'

Mud 600' to 500' Plug, Halls & 15 sacks cement 45' to 0'

Very truly yours,

Edwards Jones
Conservation Division Agent