



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-129-10084-0000

RECEIVED  
STATE CORPORATION COMMISSION

JAN 28 1963

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Herb Michaelis of Graham-Michaelis Drilling Co. has this

date requested permission to plug the following described well:

Mr. Herb Michaelis guarantees payment of the plugging fee.Operator's full Name: Graham-Michaelis Drilling Co.Complete Address: 211 North Broadway. Wichita, KansasLease Name: Matzen Well No. # 1Location: C SE/4 Sec. 35 Twp. 31S Rge. 42 (E)(W)County Morton Total Depth 5250' Oil WellGas Well X Input Well SWD Well D & A X Lost HoleMr. Herb Michaelis was instructed to plug the well as follows:8 5/8" 1458' Circulated w/cement.Mud 5250' to 3350' Spotted 50 sax.cement 3350' to 3200'Mud 3200' to 907' Plug, 35 sax.cement 907' to 812'Mud 812' to 40' Plug, 15 sax.cement 40' to surface.

Very truly yours,

*Hugh Scott*  
Conservation Division Agent