



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-129-000 18-0000

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 1 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Dungen of Superior Oil Co. has this  
date requested permission to plug the following described well:

Mr. Dungen guarantees payment of the plugging fee.

Operator's full Name: Superior Oil Company

Complete Address: Box 200, Casper, Wyoming

Lease Name: Purcell Unit Well No. 1

Location: G NW Sec. 3 Twp. 31 Rge. 42 (E) (W)

County: Morton Total Depth 5344' Oil Well

Gas Well X Input Well  SWD Well  D & A X Lost Hole

Mr. Dungen was instructed to plug the well as follows:

10 3/4" to 1522' circulated w/ cement. 7" to 5340' cemented.

Top perforations 5243' Plug bottom w/ 25 sacks cement

Top of cement 5110' Mud 5110' to 800'

Spot 60 sacks cement 800' to 700' Mud 700' to 40'

Plug, Hulls & 20 sacks cement 40' to 0'.

Very truly yours,

Edward A. Eves  
Conservation Division Agent