



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-119-2041-0000

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Amerex has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Amerex Inc.

Complete Address: 200 N. Harvey, Oklahoma City, Oklahoma

Lease Name: Hartshorn Well No. 1

Location: C NE SW Sec. 1 Twp. 31 Rge. 28 XX (E) (W)

County: Meade Total Depth 5600' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1308' circulated w/ cement. 4 1/2" to 4000' cemented.

Top perforations 3866' Plug bottom w/ 20 sacks cement.

Top of cement 3700' Mud 3700' to 1000'

Spot 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent