

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 95-18

LOCATION SE NE NE

SEC. 30 TWP. 29 SRGE. 2W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Parsons

Operator The Texas Company Address 614 Bitting Bldg., Wichita, Kans

Field \_\_\_\_\_ County Sedgwick

Total Depth 4100 Feet.

Plugging Contractor Stickel Drilling Company

Plugging Contractor's License No. not required

Address Wichita, Kansas

(Describe briefly the manner in which the well was plugged)

530 feet of 10-3/4" surface pipe circulated

with 450 sacks of cement. Filled hole full of

heavy rotary mud from 4100 feet to 480 feet. Dumped

20 sacks of cement, through the drill pipe from 480

to 440 feet. Heavy mud from 440 feet to 30 feet.

15 sacks of cement from 30 feet to top. Halliburton

pumped cement through the drill pipe.

L. S. Myer  
District Conservation Agent

**PLUGGING**  
FILE SEC 30 T 29 R 2W  
BOOK PAGE 9.5 LINE 18

DATE February 5, 1955