



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Mobil Oil Corporation

Complete Address Box 1934, Oklahoma City, Oklahoma 73101

Lease Name Carrie Young Well No. 1

Location C NE NE Sec. 11 Twp. 31 Rge. 35 (E) (W)

County Stevens Total Depth 5750'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sargent Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 11:00 AM Day 8 Month 7 Year 1974

The above well was plugged as follows:

8 5/8" to 659' circulated w/ cement. 4 1/2" to 5745' circulated w/ cement.

Topperforations 5620' Plug bottom w/ 15 sacks cement.

Top of cement 5450' Mud 5450' to 650'

Spotted 10 sacks cement 650' to 550' Mud 550' to 50'

Plug & 5 sacks cement 50' to 0'. Company Pump

No Pipe Pulled.

INVOICED

hereby certify that the above well was plugged as herein stated.

DATE 7/12/74
INV. NO. 9514-W

Signed: [Signature]
Well Plugging Supervisor