

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pan American Petroleum Corporation

Complete Address Box 432, Liberal, Kansas

Lease Name Z.M. Hille Well No. 1

Location SE NW Sec. 3 Twp. 32 Rge. 33 (E) (W)

County Seward Total Depth 6000'

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated None

Plugging Contractor Lillard Casing Pulling Co.

Address Woodward, Oklahoma License No. 618

Operation Completed: Hour 6:30PM Day 16 Month 12 Year 1969

The above well was plugged as follows:

8 5/8" to 659' circulated w/ cement. 5 1/2" to 5970' cemented.

Top perforations 4970' Plug bottom w/ Bridge Plug & 10 sacks cement.

Top of cement 4000' Mud 4000' to 1285'

Spotted 25 sacks cement 1285' to 1200' Mud 1200' to 700'

Spotted 50 sacks cement 700' to 550' Mud 550' to 60'

Plug Hulls & 25 sacks cement 60' to 0! Halliburton Pump Truck.

Pulled 1785' of 5 1/2" casing.

Set bridge plug at 4050'.

I hereby certify that the above well was plugged as herein stated.

Signed: Edna J. Evers
Well Plugging Supervisor

INVOICED
DATE 12/23/69
INV. NO. 1120-W