

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION 1250' N & 1250' E of SW Cor.

SEC. 15 TWP. 32 RGE. 32 (W)

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Roy Lambert

Operator Draper Motors Corporation Address Manhart, Millison & Beebe, Jenkins Bldg.
Tulsa, Oklahoma

Field Hugoton County Seward

Total Depth 2690 Feet.

(Describe briefly the manner in which the well was plugged)

Hole filled with heavy mud through rotary pipe, Halliburton plug at 2685'
mixed and pumped in 15 sacks of cement, placed another Halliburton plug on
top of cement and pumped top plug to 25 feet below surface level. Cut off
casing five feet below ground level, mixed and dumped five sacks of cement
in surface pipe and welded steel cap on casing. Ground has been leveled.

RECEIVED
STATE CORPORATION COMMISSION
1-19-55
JAN 19 1955

R. D. Phillips
District Conservation Agent

Date December 28, 1954

PLUGGING
FILE 15-32-32W
BOOK 87 PAGE 31