

RE KANSAS STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED STATE CORPORATION COMMISSION OCT 23 1961 10-19-61 CONSERVATION DIVISION Wichita, Kansas

TO: J. P. Roberts Assistant Director 500 Insurance Building 212 North Market Wichita 2, Kansas

File No. _____ County: Stevens

Location: CSW NE Sec. 34 Twp. 33 Rge. 36 (E) (W)

Name of Field: _____ Total Depth: 6470

I have this date completed supervision of plugging of:

Lease Name: Marford Well No. A-2

Operator's Full Name: Northern Natural Gas Producing Co.

Complete Address: 610 Union Center Bldg, Wichita, Kan.

Plugging Contractor: Wesley Bass

Address: Wichita Falls, Texas License No. _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 10pm Day 16 Month 10 Year 1961

The above well was plugged as follows:

649' of 8 1/2" surface casing. Hole filled to 6250' with heavy mud. 90 sack cement spotted from 6250' to 5900'. Mud to 3025'. 130 sack cement spotted from 3025' to 2550'. Mud to 655'. 15 sack cement spotted from 655' to 600'. Mud to 35'. Cement plug at 35' and 15 sack cement to base of collar.

Signed: [Signature] Conservation Division Agent

Reviewed: [Signature] Field Supervisor

Remarks:

INVOICED DATE 11/1/61 INV. NO. 3985-W