

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 20 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Mobil Oil Corporation  
Complete Address Box 400, Hugoton, Kansas  
Lease Name Wallace Well No. 1  
Location SE SE NW Sec. 12 Twp. 33 Rge. 35 (E) (W)  
County Stevens Total Depth 2786'  
Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A X  
Other well as hereafter indicated None  
Plugging Contractor J.D. Well Service  
Address Liberal, Kansas License No. 632  
Operation Completed: Hour 4:30PM Day 8 Month 7 Year 1971

The above well was plugged as follows:

8 5/8" to 550' circulated w/ cement. 5 1/2" to 2786' cemented  
Perforations UNKNOWN. Plug bottom w/ sand to 1637' & 50 sks cement.  
Top of cement 1300' Mud 1300' to 619'  
Spot 35 sacks cement 619' to 400' Mud 400' to 60'  
Plug. & 15 sacks cement 60' to 0'. Halliburton Pump Truck.  
No Pipe Pulled

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 7-20-71  
INV. NO. 4017-W