

15-189-00013-0001

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 24 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
11-24-69

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Shell Oil Company

Complete Address: 1700 Broadway, Denver, Colorado 80202

Lease Name L.W. Sandy Well No. 1-17

Location NE SW Sec. 17 Twp. 33 Rge. 35 (E) (W)

County Stevens Total Depth 5320'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Co.

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 3:00PM Day 19 Month 11 Year 1969

The Above well was plugged as follows:

8 5/8" to 670' circulated w/ cement. 4 1/2" to 5240' cemented

Top perforations 5056' Plug bottom w/ Bridge Plug set at 4900'

Mud 4900' to 600' Spotted 35 sacks cement 600' to 500'

Mud 500' to 45' Plug, Hulls & 15 sacks cement 45' to 0'

Company Pump

Pulled 2320' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar J. Evers  
Well Plugging Supervisor

DATE 11/24/69

INV. NO. 901-U