

15-189-00350-0000

R  
KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 24 1960  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
Jewel M. Ogden, Director,  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ Location: SE 40 NW 1/4  
County: Stevens Sec. 27 Twp. 33 Rge. 35 (E) (W) \_\_\_\_\_  
Name of Field or Pool: Hugoton Total Depth: 2,860 ft.

I have this date completed supervision of plugging of:

Well No. # 1 Lease Hilbig "A"

Operator's Full Name NORTHERN NATURAL GAS PRODUCING CO.

Complete Address: 2223 DODGE ST. OMAHA, NEBRASKA

Plugging Contractor: DAGO LEASE & WELL SERVICE

Address: 1700 S. MAIN ST. BORGER, TEXAS License No. 138

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

If well is a rotary drilled dry hole did operators wait for you to arrive \_\_\_\_\_

If yes how long \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 1:00 P.M. Day 7 Month May Year 1960

The above well was plugged as follows:

Spot 30 sacks common cement at 628 ft. (Shot-spot) Displace same with 15 bbls mud.  
(from 624 ft. to 515 ft.)

Fill 8-5/8" surface pipe with mud to within 30 ft. of top and spot 30 sacks common  
cement from 30 ft. down to top of surface for plug and cap on top.

Note: Packer set with 2 1/2" tubing @ 1,981 ft. & cemented from that point (1981) to  
TD (2860).  
Temperature survey revealed top of cement on long string (5 1/2") @ 760 ft.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: [Signature]  
Well Plugging Contractor

Signed: [Signature]  
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Reviewed: [Signature] Field Supervisor  
Remarks: \_\_\_\_\_  
Signed: \_\_\_\_\_  
INVOICED  
DATE 5/26/60  
INV. NO. 1415-4  
Well Plugging Supervisor