

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 99-5-

LOCATION CE. SW. SW.

SEC. 2 TWP. 30 RGE. 4 West.

Dry Hole _____ Abandoned Oil Well x ^{Then made into a SWD. Well} Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. One Lease SCHAMMERHORN.

Operator Magnolia petroleum Co. Address Box 770 Great Bend Kansas

Field _____ County Sumner..

Total Depth 4611 Feet.

(Describe briefly the manner in which the well was plugged)

Filled hole 100 Ft with sand and dumped 6sacks Cemenet on top of it

hot pipe off at 3743. then mudded and shot pipe off at 3400

Dumped 6sacks Cemenet pulled pipe and mudded to. 250 set bridge and dumped 25 sacks Cemenet then mudded to Below Celer. then filled to top with cemenet All the seurface pipe is in this well and 2500 ft of 7 $\frac{1}{2}$ and About 1129 ft of 5 $\frac{1}{2}$ left in the well.

The mud was good and this well should be well plugged as none of gas showed up. any plce above the 1800 ft stuff...

RECEIVED
STATE CORPORATION COMMISSION
JUL 17 1953 7-17-53
PLUGGING
FILE SEC 2 T 30 R 40
BOOK PAGE 99 LINE 5
CONSERVATION DIVISION
Wichita, Kansas

W. Y. Buffington
District Conservation Agent

Date June.. 30--53...