

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 51--5

LOCATION NE-NE--SW--

SEC. 22 TWP. 30 RGE. 1 West.

Dry Hole \_\_\_\_\_ Abandoned Oil Well YES Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. ONE Lease ~~WILLIE.~~ Wille

Operator Petroleum Inc. Address 305 East third st Wichita Kansas.

Field \_\_\_\_\_ County Sumner.

Total Depth 3941 Feet.

(Describe briefly the manner in which the well was plugged)

Filled with sand from 3942 to 3910. Run 5 sacks Cemenet filling to  
3875 Filled with mud to. bottom of Surface pipe at 367 ft then rock  
to. 340 with 14 sacks Cemenet filling to 300 then mud to 40  
and rock to 25' then filled with 7 sacks Cemenet into Cellar  
Only got 3172 ft of 5 1/2 ft of pipe out.

*W G Buffington*  
District Conservation Agent

Date Oct 22--52...

RECEIVED  
CORPORATION COMMISSION

NOV - 3 1952 11-3-52

CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
FILE SEC 22 T 30 R 124  
BOOK PAGE 57 LINE 5