

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. NEW

LOCATION NW--NW0--SW

SEC. 24 TWP. 30 RGE. 1 West

Dry Hole YES Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. ONE Lease PARKER

Operator Franco-Central Oil Co Address 4 National Bank Wichita

Field _____ County SUMNER KANSAS

Total Depth 3900 Feet.

(Describe briefly the manner in which the well was plugged)

Heavy Mud from bottom up and into the Surface pipe at 250 Ft then
set Halliburton Plug then bridged then dumped 15 Sacks Cemenet
then heavy mud to 30 ft of top then set h lliburton Plug
and bridged then dumped 10 sacks Cement filling to ground
leavel then welded cap on top of 8.5/8 Surface pipe at ground leavel

PLUGGING
FILE SEC 24 T. 30 STATE CORP
BOOK PAGE 128.1 E. 40

RECEIVED
27 1956

12-27-56

W. G. Buffington
District Conservation Agent

CONSERVATION DIVISION
Wichita, Kansas

Date Dec. 25--1956.