


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sumner County. Sec. 23 Twp. 30 Rge. (E) 3 (W)
Location as "NE/CNW/SW" or footage from lines. NW NW NW
Lease Owner E. H. Adair Oil Co.
Lease Name Tretthar Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-24-63 19__
Application for plugging filed 8-24-63 19__
Application for plugging approved 8-24-63 19__
Plugging commenced 8-24-63 19__
Plugging completed 8-24-63 19__
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4269 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Copy of Drillers Log attached hereto.						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole to 200 feet with 40 viscosity mud. Set dry hole plug- added 1/2 sack hulls and 20 sacks of cement. Filled hole from top of cement to 25 feet of surface, set a plug and added 1/4 sack of hulls and eight sacks of cement. Put two sacks of cement in the rat hole.

RECEIVED
STATE CORPORATION COMMISSION

SEP 4 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E. H. Adair
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Sherrill Compton (employee of owner) or XXXXXX of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Sherrill Compton
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of September, 19 63

My commission expires 9-15-65 L. Hill Notary Public.

E. H. Adair Oil Company
1005 East Second Street
Wichita 14, Kansas.

E. H. Adair Oil Company
No. 1 - Trotter
NW 1/4 NW 1/4 of
Sec. 23-Twp. 30 S.-Rge. 3 E.,
Sumner County, Kansas.

Elevation: 1,516 K.D.

Comm.: 8-10-63
Comp.: 8-23-63
Contractor:
Adair - Rig No. 3
8-5/8 in. s/cog. #
250 ft. w/187 sax.
Pro. D. & A.

Figures indicate bottom of formations:

Line and shale to	2700
Shale	2877
Sand	3013
Shale	3185
Line	3409
Shale and lime	3475
Line	3552
Shale and lime	3610

Line to	3651
Shale and lime	3708
Shale	3804
Line and chert	4178
Line	4187
Shale	4260
Sand	4269
T.D.	4269

Schlumberger Tops:

UTAHAKER	2877 (-1541)
KANSAS CITY	3185 (-1849)
BASS KANSAS CITY	3409 (-2073)
FORT SCOTT	3475 (-2139)
MISSISSIPPI	3804 (-2468)
LINDERBROOK	4187 (-2851)
SIMPSON SAND	4260 (-2924)
T.D.	4269

DST No. 1, 4254-49

Packer failure.

DST No. 2, 4262-69

Open one (1) hour. Recovered 1,800 feet of saltwater.

IRBP - 1,598 lbs. in 20 min.;

IRBP - 1,598 lbs. in 30 min.;

IRP - 17 lbs.

IRP - 824 lbs.

Certified correct:

RECEIVED
STATE CORPORATION COMMISSION

SEP 4 1968

CONSERVATION DIVISION
Wichita, Kansas

Sherrill Compton
Sherrill Compton - Geologist.