

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-175-20452-0000

LEASE NAME B. H. Lemert B

WELL NUMBER 1

4950 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 27 TWP. 32S RGE. 33 (E) or (W)

COUNTY Seward

Date Well Completed 4-12-87

Plugging Commenced 6-25-87

Plugging Completed 6-30-87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Amoco Production Co.

ADDRESS P. O. Box 432 Liberal, KS 67901

PHONE#(316) 624-6241 OPERATORS LICENSE NO. 5952

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, KS

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation St. Louis Depth to Top 5870 Bottom 5999 T.D. 5999

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	1586	0 (Surface)
St. Louis	Oil	5870	5999	5-1/2	5999	2620 (Production)

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
CIBP set @4686', pump 50 sxs cmt 2600' to 2450', mud to 1630' pump 50 sxs cmet 1630' to 1530', mud 1530' to 800' pump 35 sxs. Cmt 800' to 700' mud 700' to 40. Put bridge and 10 sxs cmt 40' to 5'. Cut off 8-5/8, 5' below ground level and cap same

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497


Address Box F Sublette, KS 67877

STATE OF Kansas COUNTY OF Haskell, ss.

R. L. Hiatt (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. L. Hiatt

(Address) P. O. Box 432



SUBSCRIBED AND SWORN TO before me this 20th day of July, 19 87

STATE OF KANSAS V. K. Bruce V. K. Bruce

Notary Public

Expires: 4-28-89 22 1987