

200 Colorado Derby Building  
Wichita, Kansas 67202

API # 15 189-20,618-0000  
LEASE NAME H.E. Shuler

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER # 3

SPOT LOCATION C W/2

SEC. 16 TWP. 31 RGE. 35 (E or W)

COUNTY Stevens

Date Well Completed 11-82

Plugging Commenced 12-4-1990

Plugging Completed 12-4-1990

LEASE OPERATOR Mobil Oil Corporation

ADDRESS 2319 N. Kansas, Liberal, Ks. 67901

PHONE # (316) 626-1100 OPERATORS LICENSE NO. \_\_\_\_\_

Character of Well Gas  
(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation Council Grove Depth to top 2954' bottom 3015' T.D. 3070'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				8 5/8"	712'	0'
Production				5 1/2"	3070'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 3 Skcs. hulls - 25 Skcs. cement, 4 Sjs. Gel - 25 Skcs. cement - 4 Skcs. Gel & 25 Skcs. cement - 2 skcs. Gel & 10 Skcs. cement. Fill 8 5/8" with 24 Skcs. cement from 184' to 5'. Cut off 8 5/8" and 5 1/2" and weld on plate. Cement plugs @ 2954' to 2530' - 1700' to 1380' - 800' to 480' & 100' to 5'. Pressured to 700 lbs.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497

Address Box E, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves (employee of operator) or  
(~~operator~~) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

**SONDRA L. EVES**  
NOTARY PUBLIC - STATE OF KANSAS  
My Appt. Exp. 12-6-92

RECEIVED  
STATE CORPORATION COMMISSION

(Signature) Edgar J. Eves

DEC 12 1990 (Address) Box E, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 6 day of Dec., 1990

Conservation Division  
Wichita, Kansas

Sondra L. Eves  
Notary Public

My Commission expires: 12-6-92