

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-189-2/185-00-00

LEASE NAME H.E. Shuler

WELL NUMBER #2

990 Ft. from S Section Line

4292 Ft. from E Section Line

SEC. 16 TWP 31S RGE 35W (E) or (W)

COUNTY Stevens

Date Well Completed \_\_\_\_\_

Plugging Commenced 9-6-02

Plugging Completed 9-11-02

LEASE OPERATOR Westport Oil & Gas Company L.P.

ADDRESS 8908 S. Yale, Ste 340, Tulsa, OK 74137

PHONE# 918, 481-6020 OPERATORS LICENSE NO. 33002

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-27-02 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes (if not, is well log attached? \_\_\_\_\_)

Producing Formation Chester Depth to Top 5966 Bottom 5994 T.D. 6250

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Chester	Oil, Gas Water	5966	5994	8 5/8	1766	-0-
				5 1/2	6250	1228
				2 7/8	6100	6100

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Mud was circulated thru tubing into the 5 1/2" casing from 6100' to surface, CIBP was set @ 5900' w/2sxcement on top, 20sx cement was pumped inside 5 1/2" casing from 1800' to 1650', Casing was cut off @ 1228', 50sx cement was pumped from 1230' to 1080', 40sx cement was pumped from 550' to 450', 10sx cement was pumped from 40' to surface (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Jerry Dunkin Well Services, Inc. License No. 8733

Address PO Box 389 Enid, OK 73702

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: \_\_\_\_\_

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jerry Dunkin


(Address) 8908 S. Yale, Ste 340, Tulsa, OK

SUBSCRIBED AND SWORN TO before me this 16th day of Sept 2002

Cathy Blackwell  
Notary Public

My Commission Expires: 5-21-05

#01008507



QR