

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 189-20758-0000

LEASE NAME Henshaw

WELL NUMBER 3

SPOT LOCATION C-NW 1/4

SEC. 18 TWP. 31 RGE. 35 ~~XXX~~ (W)

COUNTY Stevens

Date Well Completed \_\_\_\_\_

Plugging Commenced 4-25-1989

Plugging Completed 4-25-1989

LEASE OPERATOR Mobil Oil Corp.

ADDRESS P.O. Box 5444, Denver, CO 80217

PHONE # (316) 356 2113 OPERATORS LICENSE NO. 5208

Character of Well GAS  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation Council Grove Depth to top 2910 bottom 2938 T.D. 3125

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Put In
Surface				8 5/8"	814'	0'
Production				5 1/2"	3125'	0'

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 4 1989

CONSERVATION DIVISION  
WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Pump 2 sks. hulls and 25 sks. cement to 2600'

Mid to 1500' - Pump 25 sks. cement 1500' to 1300'

Mud to 800' - Pump 25 sks. cement 800' to 600'

Mud to 40' - Put bridge and 5 sks. cement 40' to 5'

Pressured to 400 lbs.

Cut off 8 5/8" and 5 1/2", 5' below ground level and cap

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest casing Pulling License No. 6497

Address Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves (~~employee of operator~~) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 26th day of April, 1989

Sondra L. Eves  
Notary Public

My Commission expires: 12-6-92