

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-20615 - 0000

LEASE NAME Hinshaw Estate

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR Mobil Oil Corporation

SEC. 18 TWP. 31 RGE. 35 X (W)

ADDRESS P.O. Box 5444 Denver, CO 80217

COUNTY Stevens

PHONE# (303) 298-2696 OPERATORS LICENSE NO. 5208

Date Well Completed

Character of Well D&A

Plugging Commenced 4-21-86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-21-86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3063

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8-5/8"	723'	0'
Production				5-1/2"	3034'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 3 sxs bulls, 2 sxs gel, 6 sxs cmt, Top 2820', pump 36.5 bbls mud to 1340'. Pump 7 sxs cmt, top 1290', 5.5 bbls mud to 1065' and 6 sxs cmt to 1015', 6 bbls mud to 773' and 12 sxs cmt to 673', 15 bbls mud to 58 and 6.3 sxs cmt 58' to 4'. Cut off csg 4' below ground level. All cmt class A.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497

Address Box F Sublette, KS 57877

STATE OF Colorado COUNTY OF Denver, ss.

STATE CORPORATION COMMISSION

MAY 22 1986

J. E. Dawson

(Employee of Operator) of (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J. E. Dawson J. E. Dawson

(Address) Production Accounting Supervisor
P. O. Box 5444 Denver, CO 80217

SUBSCRIBED AND SWORN TO before me this 19th day of May, 19 86

Mark Ellen McIsland
Notary Public

My Commission Expires: 6/16/88