

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-189-21,398-0000

LEASE NAME Gaskill

WELL NUMBER 1-21

4950 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 21 TWP. 31 RGE. 35 (E) or (W)

COUNTY Stevens

Date Well Completed 12/16/89

Plugging Commenced 12/16/89

Plugging Completed 12/17/89

LEASE OPERATOR Lance Ruffel Oil & Gas Corp.

ADDRESS 100 Park Ave. Bldg, Ste 500, Okla City OK

PHONE#(405) 239-7036 OPERATORS LICENSE NO. 30243

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/16/89, plugging permit # 15-189-21398 (date)

by Glenn Barlow/Liberal (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation None Depth to Top _____ Bottom _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled
Chase	probable Gas & H ₂ O	2546	2874	Conductor	40'	-0-
Council Grove	Water	2874	3134	13-3/8"	596'	-0-
Ardmore	Water	3134	3284	8-5/8"	1237'	-0-
Wabanasee	Water	3284	3664			
Shawnee	Water (over)	3664	4077			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
 12/17/89: TD 6100'. DAY 17. CEMENT DETAIL: Dowell cmtd w/100 sx @ 2600'; 50 sx @ 1730'; 40 sx @ 800'; 10 sx @ 40'; 10 sx in mouse hole; 10 sx in rat hole. HRS: 3 trp; 7 LDDP; 1-1/2 pg; 7 WOO: 5-1/2 WO Dowell pmp trk. Finished pg @ 9:30 A.M. 12/17/89.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Dowell License No. _____

Address Box 887 Ulysses KS 67880

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lance Ruffel Oil & Gas Corp.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Jim Trepagnier (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim Trepagnier

(Address) 100 Park Ave. Bldg. Ste 500
 Okla City OK 73102

SUBSCRIBED AND SWORN TO before me this 18 day of Dec., 19 89

Carla A Johnson
 Notary Public

My Commission Expires: Sept. 24, 1992

(continued).

Heebner	Water	4077	4213
Lansing	Water	4213	4467
Kansas City	Water	4467	4907
Marmaton	Water	4907	5100
Cherokee	Water	5100	5474
Morrow Shale		5474	5778
Chester	Water	5778	5953
Chester SS	water ?	5953	5996
St Genevieve	Water ?	6007	