

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-175-20310-0000

API NUMBER \_\_\_\_\_

LEASE NAME Edna Scott

WELL NUMBER #2

1980 Ft. from N Section Line

1980 Ft. from E Section Line  
NE/4

SEC. 15 TWP. 32S RGE. 33W (E) or (W)

COUNTY Seward

Date Well Completed \_\_\_\_\_

Plugging Commenced 4-15-93

Plugging Completed 4-21-93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Hugoton Energy Corporation

ADDRESS 229 E. Williams #500, Wichita, Ks. 67201

PHONE# (316) 262-1522 OPERATORS LICENSE NO. 3871

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Glenn Ward (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, Is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 6060'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
					1620'	none
					5150'	3198'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Pumped bottom to 4960' with 25 sacks cement. Shot pipe @3500', 3411', 3200', pulled up to 2900', pumped 80 sacks cement, pulled to 1650' and pumped 50 sacks, pulled to 700' and pumped 40 sacks, pulled to 40', pumped 10 sacks, circulated cement to surface. 60/40 pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hugoton Energy Corporation

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) of \_\_\_\_\_

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 26th day of April, 1993

Irene Herzberg  
Notary Public

My Commission Expires: \_\_\_\_\_



RECEIVED  
STATE CORPORATION COMMISSION  
MAY - 3 1993  
CONSERVATION DIVISION  
Wichita, Kansas