

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-175-20,230-  
0000  
LEASE NAME Edna Scott  
WELL NUMBER #1 & G.U. B#1  
SPOT LOCATION SE-SE  
SEC. 15 TWP. 32 RGE. 33 (E) or (W)  
COUNTY Seward  
Date Well Completed 9-20-1976  
Plugging Commenced 11-2-1989  
Plugging Completed 11-8-1989

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Amoco Production Co.  
ADDRESS Box 800, Rm. 1846, Denver CO 80201  
PHONE # (303) 830-5025 OPERATORS LICENSE NO. 5952

Character of Well Oil & gas  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation Kansas City Depth to top 4810' bottom 4826' T.D. 6109'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				9 5/8"	1890'	0'
Production				7"	6109	2430'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 2 Skcs. hulls & 30 Skcs. cement to 4600'

Set CIBP @ 2924' - capped w/2 sks. cement. Pumped 50 sks. cement 2400' to 2300'  
Mud 2300' to 1940' - pump 50 sks. cement 1940' to 1840' - mud 1840' to 600'  
Pump 50 sks. cement 600' to 500' - put bridge & 10 sks. cement 40' to 5'  
Cut off 9 5/8", 5' below surface and cap.  
(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor MIDWEST CASING PULLING SERVICE License No. 6497  
Address Box F, Sublette, Ks. 67877

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF HASKELL, ss.

NOV 13 1989

L. Edgar J. Eves (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) L. Edgar J. Eves  
(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 10th day of Nov., 19 89

Sondra L. Eves  
Notary Public

My Commission expires: 12-6-92