

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

20457  
API NUMBER 15-175-20475-0000

LEASE NAME Edna Scott

WELL NUMBER 3

SPOT LOCATION C, NE, SE

SEC. 15 TWP. 32 RGE. 33 (W) or (E)

COUNTY Seward

Date Well Completed 8-23-80

Plugging Commenced 10-7-85

Plugging Completed 10-18-85

LEASE OPERATOR Amoco Production Company

ADDRESS P. O. Box 432 Liberal, KS 67901

PHONE #(316) 624-6241 OPERATORS LICENSE NO. 5952

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #1 302 West McArtor, Dodge City, KS

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing formation Chester Depth to top 5780 bottom 5792 T.D. 6000

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Chester	Oil	5708	5832	8-5/8	1616	
				5-1/2	6000	2530'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Set CRP at 5700' and cap with 2 sxs cement. Shot casing at 2530', worked loose. Loaded with mud and followed with 50 sxs cement on stub 2530' to 2380'. Layed down 5-1/2" to 1676'. Pump 50 sxs cement 1676' to 1526' followed with mud. Layed down rest of 5-1/2" - 60 lbs - Cut off 8-5/8" below ground level. Put bridge with 10 sxs cmt 40' to 0'. Weld plate on 8-5/8".  
40 sxs cmt @ 740' info from J. Sanders S-27-86 - DR  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing and Pulling License No. \_\_\_\_\_  
Address Box F Sublette, KS 67877

STATE OF Kansas COUNTY OF Seward, ss.

P. A. Lehrman (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) P. A. Lehrman

(Address) P. O. Box 432 Liberal, KS 67901


SUBSCRIBED AND SWORN TO before me this 31<sup>st</sup> day of Oct, 1985

V. K. Bruce  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

NOV 1 1985

Form CP-4 1-84  
Revised 06-83



CONSERVATION DIVISION