

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15 175 20309-0000

LEASE NAME Hattie Jones

WELL NUMBER 1

660 Ft. from S Section Line

3400 Ft. from E Section Line

SEC. 15 TWP. 32S RGE. 33 (E) or (W)

COUNTY Seward

Date Well Completed 6-77

Plugging Commenced 7-20-87

Plugging Completed 7-23-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Amoco Production Co.

ADDRESS P. O. Box 432

PHONE# (316) 624-6241 OPERATORS LICENSE NO. 5952

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Marmaton Depth to Top 4874 Bottom 5032 T.D. 5100

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Marmaton	Oil	4874	5032	8-5/8	1586	0 (Surface)
				5-1/2	5118	2615 (Production)

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Set CIBP @4710, pump 50 sxs cmt 2600' to 2450, mud 2450 to 1630 pumped 40 sxs cement
1630' to 1530' mud 1530 to 800
Pumped 40 sxs cement 800 to 700 mud 700 to 40
Bridge and 10 sxs 40' to 5' - Cut off 8-5/8 5' below ground level and cap
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497

Address Box F Sublette, KS 67877


STATE OF Kansas COUNTY OF Haskell, ss.

Larry L. Smith *Larry L. Smith* (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) _____

(Address) P. O. Box 432

SUBSCRIBED AND SWORN TO before me this 5th day of August, 19 87



V.K. Bruce Notary Public

Appointment Expires: 4-28-89

RECEIVED
STATE CORPORATION COMMISSION
AUG. 7 v. 1987
K. Bruce
CONSERVATION DIVISION
Wichita, Kansas