

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Morgan

WELL NUMBER 2-5

3300 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 5 TWP. 32S RGE. 33W (E) or (W)

COUNTY Seward

Date Well Completed 2-10-69

Plugging Commenced 4-8-88

Plugging Completed 4-10-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 29, 1988 (date)

by Shari Feist (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes (Drillers Log)

Producing Formation Hugoton Depth to Top 2547

RECEIVED
STATE CORPORATION COMMISSION
D. 2685

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

AUG - 3 1988

Formation	Content	From	To	Size	Put In	Conserved out
Hugoton	gas	2547	2668	8-5/8"	576'	540'
				4-1/2"	2685'	

CONSERVED out
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Cement retainer set at 2602'. Pumped 20 sxs common on top of retainer to 2350'.

Pumped 20 sxs of common cement 1300-1100'. Pumped 60 sxs common cement 540-400'.

Pumped 10 sxs cement 40-0'. Cut off surface casing 5' below surface and capped well.

Heavy drilling mud spotted between plugs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901


STATE OF Kansas COUNTY OF Seward, ss.

David W. Kapple (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David W. Kapple

(Address) P. O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 2nd day of August, 19 88



Beverly J. Williams
Notary Public
November 21, 1990

DRILLER'S LOG

WELL NAME: Morgan No. 2 ; COMPANY OPERATING: Panhandle Eastern Pipe Line Company
C S/2 NW/4 ADDRESS of COMPANY: P. O. Box 828, Liberal, Kansas 679

WELL LOCATION: XXXXXXX,
3300 ft. North of South line,
1320 ft. East of West line; Sec. 5, Twp. 32, Rge. 33, Seward County, Kansas

DRILLING STARTED 1-24, 1969; DRILLING COMPLETED 1-27, 1969
WELL COMPLETED 2-10, 1969; WELL CONNECTED 2-25, 1969

ELEVATION: 2790 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) gas

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
Herington	2542	47	10)	
U. Krider	2574	97	18)	
L. Krider	2606	12	12) 10,000	15% HCL
L. Krider	2620	24	8)	
Winfield	2654	68	28	sqz.	

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8-5/8	576	300	0
4-1/2	2684	400	0

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Cimarron	1628	1675			
Herington	2541	2548			
U. Krider	2562	2592			
L. Krider	2604	2628			
Winfield	2647	2674			

RESULTS of INITIAL PRODUCTION TEST: 24 hour blowdown gauge 1.5 MMCF