

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 12/17/57 SPUD DATE

LEASE NAME ELLIS

WELL NUMBER 1-6

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1956 Ft. from <sup>N</sup> Section Line

1980 Ft. from E Section Line

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

SEC. 6 TWP. 32S RGE. 33 (E) or (W)

ADDRESS P.O. Box 351, LIBERAL, KS 67905-0351

COUNTY SEWARD

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 1/9/58

Character of Well GAS

Plugging Commenced 6/1/94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6/6/94

The plugging proposal was approved on 6/1/94 (date)

by GLENN BARLOW (KCC District Agent's Name).

DRILLERS  
Is ACO-1 filled? LOG FILED If not, is well log attached?

Producing Formation NONE Depth to Top Bottom T.D. 2670

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	600	3'
				4 1/2	2660	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
MIRU CSG PULLERS. PUMP 2 SXS HULLS & 25 SXS CLASS "H" CMT 2639-2300. PULL 2 3/8 TBG TO 1400'. PUMP 20 SXS CLASS "H" CMT 1400-1200. PULL 2 3/8 TBG TO 620'. PUMP 40 SXS CLASS "H" CMT 620-200'. TOH & LD 2 3/8 TBG. PUM 16 SXS CLASS "H" CMT 53-3'. CUT OFF 8 5/8 CSG 3' BELOW GL & CAP. RDMO CSG PULLERS. STATE WITNESS: GLENN BARLOW.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

Leslie I. Barnes, Sr. Technical Assistant (Employee of Operator) or ~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leslie I. Barnes  
(Address) P.O. Box 351, Liberal, KS 67905-0351

RECEIVED  
KANSAS CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 11th day of July, 19 94

CONSERVATION DIVISION  
WICHITA, KS  
Commission Expires:

CHERYL STEERS  
Notary Public - State of Kansas  
My Appl. Expires 6-1-97